

MILFORD ROAD RECONSTRUCTION PLAN																	
2018																	
ROAD												Shim		Pave			WORK
	Route Ahead	Route Back	Length	Width	SF	OCI	Miles	Reclaim (SY)	Inject	Mill (SY)	Chip(SY)	1"	Tons	1 1/2"	Tons	2"	Tons
Ponemah Hill Rd	Emerson Rd	Amherst Line	9,446	21	216,492	50.29	1.79	24,055								4,041	Reclaim/Base2"
Osgood Rd	Burns Rd	Noons Quarry Rd	4,590	23	113,465	57.05	0.87	12,607								2,118	Reclaim/Base2"
King St	George St	Osgood Rd	1090.8	19	20,239	45.44	0.21	2,249								315	Reclaim/Base2"
George St	King St	Union St	1091.33	26	26,774	63.00	0.21	2,975								416	Reclaim/Base2"
Clinton St	Nashua St	South St	1230.15	27	33,547	65.92	0.23	3,727								522	Reclaim/Base2"
Ball Hill Rd	Melendy Rd	Annand Dr	2230.76	16.00	35692.16	55.35	0.42				3,966	333					Shim/Chip
Osgood Rd	Armory Rd	Burns Rd	3370.17	22.00	74143.74	61	0.64				8,238	692					Shim/Chip
Melendy Rd	Osgood Rd	Ball Hill Rd	4453.27	22.00	97971.94	75	0.84				10,886						Chip
Elm St	Old Wilton Rd	Hitchiner Way	3,191	22	122,772	68	0.60			13,641				1,910			Mill/Fill 1.5"
Nashua St	Burger King	Ciardelli Cr	3,264	30	137,330	79	0.62			15,259				2,136			Mill/Fill 1.5"
MILFORD ROAD RECONSTRUCTION PLAN 2018 Estimate							6.43	45,613	0	28,900	23,090	1,025	0	4,046	0	7,412	0