SITE DEVELOPMENT PLANS

MILFORD FIRE STATION

TAX MAP 26, LOT 168 - 39 SCHOOL STREET

MILFORD, NEW HAMPSHIRE APRIL 24, 2018

TOWN OF MILFORD CONTACTS:

1. COMMUNITY DEVELOPMENT:

TOWN HALL 1 UNION SQUARE MILFORD, NH 03055

ATT: LINCOLN DALEY COMMUNITY DEV, DIRECTOR (603) 249 - 0620

2. DEPARTMENT OF PUBLIC WORKS:

ATT: RICK RIENDEAU PUBLIC WORKS DIRECTOR 603-673-1662

3.FIRE DEPARTMENT:

ATT: JACK KELLY FIRE CHIEF 603-249-0680

UTILITY CONTACTS:

1. WATER & SEWER:
PUBLIC WORKS DEPT.
564 NASHUA STREET
MILFORD, NH 03055
ATT: DAVE BOUCHER
WATER UTILITIES DIRECTOR
(603) 249-0660

2.GAS:
LIBERTY UTILITIES
130 ELM STREET MANCHESTER, NH 03101


ATTN: RYAN LAGASSE (603) 327-7161

3. TELEPHONE: FAIRPOINT COMMUNICATIONS 237 DANIEL WEBSTER HWY. MERRIMACK, NH 03054

ATTN: ROBERTO DIAZ (603) 595-1150

4.POWER: EVERSOURCE OF NH P.O. BOX 330 MANCHESTER, NH 03105-0330

ATTN: ALAN LEBORGNE



| SHEET INDEX | | | | | |
|-------------|-------|----------------------------|--|--|--|
| PAGE | SHEET | TITLE | | | |
| 1 | CV-1 | COVER SHEET | | | |
| 2 | SP-1 | SITE LAYOUT PLAN | | | |
| 3 | EX-1 | EXISTING CONDITIONS PLAN | | | |
| 4 | GR-1 | GRADING AND DRAINAGE PLAN | | | |
| 5 | UT-1 | UTILITY PLAN | | | |
| 6 | LT-1 | SITE LIGHTING PLAN | | | |
| 7 | SWM-1 | STORMWATER MANAGEMENT PLAN | | | |
| 8 | DT-1 | CONSTRUCTION DETAILS | | | |
| 9 | DT-2 | CONSTRUCTION DETAILS | | | |
| 10 | DT-3 | EROSION CONTROL DETAILS | | | |



PREPARED FOR PORT ONE ARCHITECTS

959 ISLINGTON STREET PORTSMOUTH, NH 03801

LAND OF TOWN OF MILFORD

> 1 UNION SQUARE MILFORD, NH 03055

Surveying + Engineering + Land Planning + Permitting + Septic Designs



LAND CONSULTANTS, PLLC

206 Elm Street, Milford NH 03055 Phone: (603)-672-5456 Fax: (603)-413-5456 www.FieldstoneLandConsultants.com




THE LOCATION OF THE UTILITIES SHOWN ARE APPROXIMA IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO LOC AND PRESERVE ALL UTILITY SERVICES.


ACTOR SHALL VERIFY ALL DIMENSIONS AND


CONTACT DIG SAFE 72 HOURS PRIOR TO CONSTRUCTION DIGSAFE.COM OR DIAL OH


PROGRESS PRINT


| | | | | | _ |
|------|------|-------------|-----|----|---|
| | | | | | _ |
| REV. | DATE | DESCRIPTION | C/0 | DR | С |
























1,500 GALLON HOLDING TANK (OR EQUAL)

1 DT-2









REV. DATE DESCRIPTION C/O DR CK

CONSTRUCTION DETAILS

MILFORD FIRE STATION

TAX MAP 26 LOT 168

39 SCHOOL STREET

MILFORD, NEW HAMPSHIRE

PREPARED FOR AND LAND OF,

TOWN OF MILFORD

1 UNION SQUARE, MILFORD, NH 03055

SCALE: AS SHOWN

APRIL 4, 2018




206 Elm Street, Milford, NH 03055

Phone: (603) 672-5456 Fax: (603) 413-5456

www.FieldstoneLandConsultants.com

FILE: 1716DT00.dwg | PROJ. NO. 1716.00 | SHEET: DT-2 | PAGE NO. 9 0F 10

- I. INSTALL SILTATION CONTROL FENCES IN LOCATIONS SHOWN HEREON. <u>EROSION AND SEDIMENTATION</u> CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY EARTH MOVING OPERATION.
- 2. INSTALL STABILIZED CONSTRUCTION EXIT(S), IF NECESSARY
- CUT AND CLEAR TREES; DISPOSE OF DEBRIS. STUMPS ARE TO BE BURIED ON SITE. STUMPS SHALL BE COMPACTED AND ALL VOIDS FILLED WITH SUITABLE MATERIAL. COVER WITH 4" OF LOAM AND SEED PER THE EROSION CONTROL NOTES.
- REMOVE TOPSOIL AND STOCKPILE AWAY FROM ANY WETLAND. STABILIZE STOCKPILE IMMEDIATELY BY SEEDING. PLACE SILT FENCE AROUND THE DOWN SLOPE SIDE OF EARTH STOCKPILES.
- . ROUGH GRADE SITE CONSTRUCT DRAINAGE LEACHING CATCH BASINS AND DRAINAGE SWALES DURING INITIAL PORTION OF CONSTRUCTION. STABILIZE IMMEDIATELY PER THE CONSTRUCTION AND EROSION CONTROL DETAILS. DO NOT DIRECT STORM WATER RUNOFF TO THESE STRUCTURES UNTIL A HEALTHY VEGETATIVE COVER IS ESTABLISHED.
- 6. BEGIN BUILDING CONSTRUCTION.
- CONSTRUCT PAVED PARKING AREAS AND BUILDING PADS. INSTALL UTILITIES AND STRUCTURES. ALL CUT AND FILL SLOPES SHALL BE STABILIZED UPON COMPLETION OF ROUGH GRADING PER THE THE EROSION CONTROL NOTE.
- 8. INSPECT AND MAINTAIN EROSION CONTROL MEASURES ON A WEEKLY BASIS AND AFTER EVERY 0.25° OR GREATER RAINFALL.
- DAILY, OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, CULVERTS, DITCHES, SILTATION FENCES, SEDIMENT TRAPS, ETC. MULCH AND SEED AS REQUIRED.
- 10. FINISH GRADING TO PREPARE FOR PAVING AND LOAMING. ALL DISTURBED AREAS SHALL BE STABILIZED WITHIN 72 HOURS AFTER FINAL GRADING.
- 11. FINISH PAVING, PERMANENT SEEDING SHALL BE PERFORMED UPON COMPLETION OF PARKING AREA (SEE EROSION CONTROL NOTES).
- 12. COMPLETE PERMANENT SEEDING AND LANDSCAPING.
- 13. TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED WHEN ALL DISTURBED AREAS HAVE BEEN STABILIZED.
- 14. ALL STRUCTURES SHALL BE CLEANED OF SEDIMENTS ONCE CONSTRUCTION IS COMPLETE.



EROSION CONTROL (GENERAL CONSTRUCTION

- PRIOR TO STARTING ANY WORK ON THE SITE THE CONTRACTOR SHALL NOTIFY APPROPRIATE AGENCIES.
- 2. EROSION CONTROL MEASURES SHALL BE INSTALLED PER PLANS AND DETAILS. PERIMETER CONTROLS SHALL BE IN PLACE PRIOR TO COMMENCEMENT OF EARTH DISTURBING ACTIVITIES
- EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE KEPT CLEAN DURING CONSTRUCTION EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE INSPECTED AT LEAST ONCE A WEEK AND AFFEE FEVERY 0.25-NOT OR GREATER RAIPFALL SEDIMENTS SHALL BE DISPOSED OF IN AN UPLAND AREA THAT WILL NOT CONTRIBUTE TO SEDIMENT OFF-SITE AND BE PERMANENTLY STABILEZED.
- 5. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION.
- DITCHES, SWALES AND DRAINAGE BASINS SHALL BE CONSTRUCTED DURING THE INITIAL PHASE OF CONSTRUCTION AND STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM.
- 8. AN AREA SHALL BE CONSIDERED STABILIZED IF ONE OF THE FOLLOWING HAS OCCURED
 - BASE COURSE GRAVELS HAVE BEEN INSTALLED IN AREAS TO BE PAVED; A MINIMUM OF BAY VEGETATED GROWTH HAS BEEN ESTABLISHED; A MINIMUM OF 3-INCHES OF NON-EROSIVE MATERIAL, SUCH AS STONE OR RIPRAP,
- EROSION CONTROL BLANKETS SHALL BE INSTALLED ON ALL SLOPES THAT ARE STEEPER THAN 3: (HORIZONTAL / VERTICAL). UNLESS OTHERWISE SPECIFIED THE CONTRACTOR SHALL USE NORTH AMERICAN GREEN SCISO, OR APPROVED EQUAL.
- ALL AREAS RECIEVING EROSION CONTROL STONE OR RIPRAP SHALL HAVE A GEOTEXTILE MATERIAL INSTALLED BELOW THE STONE (SEE APPROPRIATE DETAILS).
- 11. ALL DISTURBED AREAS TO TURF FINSHED SHALL BE COVERED WITH A MINIMUM THICKNESS OF 4 NOHES OF COMPACTED LOAM. LOAM SHALL BE COVERED WITH THE APPROPRIATE SEED MIXTURE AS INDICATED BELOW:

POUNDS / 1,000 SQUARE FEET PERMANENT SEED (LAWN AREAS)

APPLICATION RATE TOTALS 2.8 LBS PER 1,000 SF**

12. APPLY LIMESTONE AND FERTILIZER ACCORDING TO SOIL TEST RECOMMENDATIONS. IF SOIL TESTING IS NOT FEASIBLE (CRITICAL TIME FRAMES OR VARIABLE SITES) THEN APPLY FERTILIZER AT A RATE OF 11 POUNDS PER 1,000 SF AND LIMESTONE AT A RATE OF 100 POUNDS PER 1,000 SF. FERTILIZER SHALL BELOW PROSPHATE (LESS THAN 2% PHOSPHORUS).


CAUTION SHOULD BE TAKE WHEN THE PROPERTY IS LOCATED WITHIN 250 FEET OF A WATER BODY. IN THIS CASE ALL FERTILIZERS SHALL BE RESTRICTED TO A LOW PHOSPHATE, SLOW RELEASE NITROGEN FERTILIZERS. WIS THE AT LEAST 610 S. LOW RELEASE NITROGEN COMPONENT. NO FERTILIZER EXCEPT LIMESTONE SHALL BE APPLIED WITHIN 25 FEET OF THE SURFACE WATER. THESE ARE REGULATED LIMITATIONS.

- 13. PERMANENT OR TEMPORARY COVER MUST BE IN PLACE BEFORE THE GROWING SEASON ENDS (SEE WINTER CONSTRUCTION NOTES). NO DISTURBED AREAS SHALL BE LEFT EXPOSED DURING THE WINTER MONTHS.
- 14. A VIGOROUS DUST CONTROL PROGRAM SHALL BE APPLIED BY THE SITE CONTRACTOR. DUST SHALL BE MANAGED THROUGH THE USE OF WATER.
- 15. IN NO WAY ARE THE MEASURES INDICATED ON THE PLANS OR IN THESE NOTES TO BE CONSIDERED ALL INCLUSIVE. THE CONTRACTOR SHALL USE JUDGEMENT TO INSTALL ADDITIONAL EROSION CONTROL MEASURES AS SITE CONDITIONS, WEATHER OR CONSTRUCTION METHODS WARRAWIT.
- 16. FOLLOWING PERMANENT STABILIZATION, TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED AND ACCUMULATED SEDIMENTATION IS TO BE DISPOSED OF IN AN APPROVED LOCATION OUTSIDE OF JURISDICTIONAL WETLANDS.

EROSION CONTROL (WINTER CONSTRUCTION)

- ALL PROPOSED VEGETATED AREA SWIGH DO NOT EVHIBIT A MINIMUM OF 85% VEGETATED GROWTH BY OCTOBER 15TH, OR WHICH ARE DISTURBED AFTER COTOBER 15TH; MINILL BE STABILIZED STABLES OF THE STABL
- 2. ALL DITCHES OR SWALES WHICH DO NOT EXHIBIT A MINIMUM OF 85% VEGETATED GROWTH BY OCTOBER 16TH, OR WHICH ARE DISTURBED AFTER COTOBER 15TH, SHALL BE STABILIZED WITH STONE OR EROSION CONTROL BLANKETS APPROPRIATE FOR THE DESIGN FLOW CONDITIONS.
- I. AFTER NOVEMBER 15TH, INCOMPLETE ROAD OR PARKING SURFACES, WHERE WORK HAS STOPPED FOR THE WINTER SEASON, SHALL BE PROTECTED WITH A MINIMUM OF 3 INCHES OF CRUSHED GRAVEL OR PROPERLY MY ALLED RESON CONTROL BLANKETS COLVERED WITH HAY. OTHER STABLIZED OF CONTROL TO BE APPROVED BY THE APPROPRIATE AGENCIES AND THE DESIGN ENGINEER. IF CONSTRUCTION IS TO CONTROL THOUGHT WINTER MONTHS THEN THE ROAD SHOULD BE CLEARED OF ACCUMULATED SNOW AFTER EACH STORM EVENT.


EROSION CONTROL NOTES



VIEW LOOKING UPSTREAM





SECTION C-C



- STONE CHECK DAMS SHOULD BE INSTALLED BEFORE RUNOFF IS DIRECTED TO THE SWALE OR DRAINAGE DITCH.
- 3. STONE CHECK DAMS SHOULD NOT BE USED IN A FLOWING STREAM
- WHEN INSTALLING STONE CHECK DAMS THE CONTRACTOR SHALL KEY THE STONE INTO THE CHANNEL BANKS AND EXTEND THE STONE BEYOND THE ABUTMENTS A MINIMUM OF 18-INCHES TO PREVENT FLOW AROUND THE DAM.
- 6. STONE CHECK DAMS SHOULD BE REMOVED ONCE THE SWALE OR DITCH HAS BEEN STABILIZED UNLESS OTHERWISE SPECIFIED.









SECTION VIEW NOTES:

- SILT FENCES SHOULD NOT BE USED ACROSS STREAMS, CHANNELS, SWALES, DITCHES OR OTHER DRAINAGE WAYS.
- 2. SILT FENCE SHOULD BE INSTALLED FOLLOWING THE CONTOUR OF THE LAND AS CLOSELY AS POSSIBLE AND THE ENDS OF THE SILT FENCE SHOULD BE FLARED UPSLOPE.
- IF THE SITE CONDITIONS INCLUDE FROZEN GROUND, LEDGE OR THE PRESENCE OF HEAVY ROOTS THE BASE OF THE FABRIC SHOULD BE EMBEDDED WITH A MINIMUM THICKNESS OF 8 INCHES OF 3/4-INCH STONE.
- SILT FENCES PLACED AT THE TOE OF SLOPES SHOULD BE INSTALLED AT LEAST 6 FEET FROM THE TOE
 TO ALLOW SPACE FOR SHALLOW PONDING AND ACCESS FOR MAINTENANCE.
- THE MAXIMUM SLOPE ABOVE THE FENCE SHOULD BE 2:1 AND THE MAXIMUM LENGTH OF SLOPE ABOVE THE FENCE SHOULD BE 100 FEET.
- 6. REMOVED SEDIMENT SHALL BE DEPOSITED TO AN AREA THAT WILL NOT CONTRIBUTE TO SEDIMENT OFF-SITE AND CAN BE PERMANENTLY STABILIZED.
- SILT FENCES SHOULD BE REMOVED WHEN THE UPSLOPE AREAS HAVE BEEN PERMANENTLY STABILIZED.


4 DT-3






- THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT-OF-WAYS. THIS MAY REQUIRE TOP DRESSING, REPAIR AMDIOR CLEANOUT OF ANY MEASURES USED TO TRAY SEDIMENT.
- 3. THE MINIMUM LENGTH OF THE PAD SHOULD BE 75 FET, EXCEPT THAT THE MINIMUM LENTH MAY BE REDUCED TO 50 FEET IF A 3-INCH TO 6-INCH HIGH BERM IS INSTALLED AT THE ENTRANCE OF THE PROJCT SITE.
- 4. THE PAD SHOULD EXTEND THE FULL WIDTH OF THE CONSTRUCTION ACCESS ROAD OR 10 FEET, WHICHEVER IS GREATER.
- 5. THE PAD SHOULD SLOPE AWAY FROM THE EXISTING ROADWAY
- 7. THE GEOTEXTILE FILTER FABRIC SHOULD BE PLACED BETWEEN THE STONE PAD AND THE EARTH SURFACE BELOW THE PAD.
- 8. THE PAD SHALL BE MAINTAINED OR REPLACED WHEN MUD AND SOIL PARTICLES CLOG THE VOIDS IN THE STONE SUCH THAT MUD AND SOIL PARTICLES ARE TRACKED OFF-SITE.
- NATURAL DRAINAGE THAT CROSSES THE LOCATION OF THE STONE PAD SHOULD BE INTERCEPTED AND PIPED BENEATH THE PAD, AS NECESSARY, WITH SUITABLE OUTLET PROTECTION.
- 10. WHEN NECESSARY, WHEELS SHALL BE CLEANED PRIOR TO ENTRANCE ONTO PUBLIC RIGHT-OF-WAY.
- 11. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH CRUSHED STONE THAT DRAINS INTO AN APPROVED SEDIMENT TRAP OR SEDIMENT BASIN.

GRAVEL CONSTRUCTION EXIT



- TO INSTALL SACK, REMOVE CATCH BASIN GRATE AND PLACE SACK IN OPENING, HOLD OUT APPROXIMATEL SIX INCHES OF THE SACK OUTSIDE THE FRAME FOR THE LIFTING STRAPS. REPLACE THE GRATE TO HOLD THE SACK IN PLACE.
- 3. THE SACK SHOULD BE INSPECTED AFTER EVERY STORM, OR ONCE EVERY TWO WEEKS, WHICH EVER OCCURS FIRST.
- 4. THE RESTRAINT CORD SHOULD BE VISIBLE AT ALL TIMES. IF THE CORD IS COVERED WITH SEDIMENT, THE SACK SHOULD BE EMPTIED. EMPTY THE SACK AWAY FROM THE CATCH BASIN TO PREVENT SEDIMENT FROM RE-ENTERING THE CATCH BASIN. EMPTY THE SACK PER THE MANUFACTURES RECOMMENDATIONS.
- REPLACE THE SACK IN THE CATCH BASIN AFTER THE SACK HAS BEEN EMPTIED. ONCE CONSTRUCTION IS COMPLETE AND ALL DISTURBED AREAS HAVE BEEN STABILIZED BY PAVING OR A HEALTHY VEGETATIVE COVER REMOVE THE SACK FROM THE CATCH BASINS.

SCALE: N.T.S. 6 DT-3 SILT SACK SEDIMENT FILTER



- DIMENSIONS GIVEN IN THIS DETAIL ARE EXAMPLES: DEVICE SHOULD BE INSTALLED PER MANUFACTURER'S SPECIFICATIONS.
- INSTALL STRAW/COCONUT FIBER EROSION CONTROL MAT SUCH AS TENSAR NORTH AMERICAN GREEN RollMax Systems' EroNet \$150 OR EQUAL ON ALL SLOPES EXCEEDING 3' HORZ: 1'VERT.
- 3. THE EROSION CONTROL MATERIAL(S) SHALL BE ANCHORED WITH "U" SHAPED 11 GAUGE WIRE STAPLES OR WOODEN STAKES WITH A MINIMUM TOP WIDTH OF 1 INCH AND LENGTH OF 6 INCH.
- SLOPE SURFACE SHALL BE FREE OF ROCKS, CLODS, STICKS AND GRASS. MATS / BLANKETS SHALL HAVE GOOD SOIL CONTACT.
- 5. APPLY LIME, FERTILIZER AND PERMANENT SEEDING BEFORE PLACING BLANKETS
- BEGIN AT THE TOP OF THE SLOPE BY ANCHORING THE BLANKET AS SHOWN. ROLL THE BLANKETS DOWN
 THE SLOPE. ALL BLANKETS MUST BE SECURELY FASTENED TO SOIL SURFACE BY PLACING STAPLES OR
 STAKES IN APPROPRIATE LOCATIONS. REFER TO MANUFACTURERS STAPLE GUIDE FOR CORRECT
 STAPLE PATTERN.
- 7. LAY BLANKETS LOOSELY AND STAKE OR STAPLE TO MAINTAIN DIRECT CONTACT WITH THE SOIL. DO NOT STRETCH.
- 8. IN LOOSE SOIL CONDITIONS THE USE OF STAPLES OR STAKE LENGTHS GREATER THAN 6 INCHES MAY BE NECESSARY TO PROPERLY SECURE THE BLANKETS.
- 9. THE CONTRACTOR SHALL MAINTAIN THE BLANKET UNTIL ALL WORK ON THE CONTRACT HAS BEEN COMPLETED AND ACCEPTED. MAINTENANCE SHALL CONSIST OF THE REPAIR OF AREAS WHERE DAMAGED BY ANY CAUSE. ALL DAMAGED AREAS SHALL BE REPAIRED TO REESTABLISH THE COND AND GRADO OF THE SOIL PRIOR TO APPLICATION OF THE COVERING AND SHALL BE REFERRILIZED, RESEEDED AND REMULCHED AS DIRECTED.

EROSION BLANKETS - SLOPE INSTALLATION



PROGRESS PRINT C/O DR CK

EROSION CONTROL DETAILS MILFORD FIRE STATION

TAX MAP 26 LOT 168 39 SCHOOL STREET MILFORD, NEW HAMPSHIRE PREPARED FOR AND LAND OF TOWN OF MILFORD 1 UNION SQUARE, MILFORD, NH 03055

SCALE: AS SHOWN

APRIL 4, 2018

Surveying & Engineering & Land Planning & Permitting & Septic Designs



FIELDSTONE LAND CONSULTANTS, PLLC

206 Elm Street, Milford, NH 03055 Phone: (603) 672-5456 Fax: (603) 413-5456

FILE: 1716DT00.dwg PROJ. NO. 1716.00 SHEET: DT-3 PAGE NO. 10 OF 10